



Bancroft®
5.5' Whirlpool Bath
K-1158-HB



Features

- End drain.
- 65-7/8" (1673 mm) x 41-3/4" (1060 mm) x 22" (559 mm)

Material

- Acrylic

Hydrotherapy

- Variable-speed pump for adjusting hydromassage intensity.
- Multiple pump location options give you more choices for installation and access.
- Built-in 1500 W heater.
- Eight fully adjustable Flexjet™ hydrotherapy jets for water flow and direction.
- Remote control.

Installation

- Drop-in
- Coordinates with other products in the Bancroft® collection.

Recommended Accessories

K-7161-AF Bath Drain
K-24916 Wireless Music Kit
K-1703 Whirlpool Remote Control
K-7265 Clearflo Bath Drain
K-9497 2-1/2" Keypad Trim
K-9698 Flexjet® Whirlpool Trim Kit
K-37382 45" Rough-in Cable Bath Drain







Codes/Standards

ASME A112.19.7/CSA B45.10
CSA B45.5/IAPMO Z124
ASTM E162
ASTM E662
UL 1795
Greenguard UL 2818 - Gold

KOHLER® One-Year Limited Warranty

See website for detailed warranty information.

No change in measurements if connected with drain illustrated. (K-7161-AF)



Required Electrical Service

One dedicated circuit required, protected with Class A Ground-Fault Circuit-Interrupter (GFCI) or Residual Current Device (RCD).

Pump, Heater: 240 V, 20 A, 50/60 Hz

Technical Information

All product dimensions are nominal.

Installation: Drop-in
Drain location: End
Basin area, bottom: 46" x 30" (1168 mm x 762 mm)
Basin area, top: 57" x 34" (1448 mm x 864 mm)
Weight: 130 lbs (59 kg)
Minimum floor load: 50 lbs/ft² (244.1 kg/m²)
Water depth: 16" (406 mm)
Water capacity: 95 gal (359.6 L)
Electrical component rating: Pump: 240 V, 11 A, 50/60 Hz
Heater: 240 V, 6.25 A, 50/60 Hz, 1500 W
Pump speed: Variable
Minimum flat for door: 0" (0 mm)

Notes

Measure your actual product for rough-in details.

Install this product according to the installation instructions.

The hot water supply should be 70% of the capacity of the bath or greater. Installations will vary.

This bath is designed for drop-in installation only. It is not suited for use in a three wall alcove with an overhead shower.

Pump must be relocated to custom position at the time of installation. Provide adequate clearance.